

## Bill of Materials

- ~1060' 8" PE Main
- ~7340' of 4" PE Main
- 8" PE Cap
- 8" Full Flow Tee
- 8" x 6" Reducer
- 6" x 4" Reducer
- 4" PE Cap

Install all main outside of fenced area.

\*Depicted locations are approximate only, and may have to be adjusted due to a variety of factors.



AMEREN MISSOURI  
GAS OPERATIONS  
2001 Maguire Blvd  
Columbia, MO 65201



### S Airport Dr Main Extension

Columbia, MO

#### INSTALLATION METHOD:

- Inserted
- Direct Bury
- Joint Trench

If Trenchless Installation Method is used, Sewer Verification in CLICK is required.

- Trenchless (Bore, Hog, etc.)
- Sewer Verification entered in CLICK

#### LEGEND

- New Main
- - - New Service
- - - Retired Main
- Existing Main
- - - Existing Service
- ⊗ New Valve
- ⊗ Existing Valve

DATE

December 17, 2020

REVISIONS

NO.	DESCRIPTION

NOTES


DESIGN: TAS DRAWN: TAS

S Airport Dr

SHEET

1 of 1

WO# DOJM#