

October 21, 2025

Mr. Matthew Kriete
Engineering Surveys & Services
1113 Fay Street
Columbia, Missouri 65201

Via Email: mkriete@ess-inc.com

Re: PD Plan & Preliminary Plat, Centerstate East Subdivsion (Minor Amendment)

Dear Mr. Kriete:


By means of this letter I am approving your request for a minor amendment to the PD development plan known as the, "PD Plan & Preliminary Plat, Centerstate East Subdivision", bearing your seal dated October 17, 2025.

Approved changes include the following:

- 1. Common stormwater management added to Lot 3.
- 2. East boundary of Lot 5, 6, 7, and 10 moved to match east edge of existing sanitary sewer easements. Sewer easements are now outside preservation lot.
- 3. Revised Creekwood Parkway alignment for design speed.
- 4. Utility lines & easements have been updated to maintain 10-ft separation from water lines and prevent water lines from running parallel under pavement.
- 5. Sanitary sewer location has been updated to serve Lots 1 and 2.
- 6. Improvements on Lot 5 & 6 rotated to eliminate potential impact to wetlands along Hinkson Creek.
- 7. Additional landscape islands were added within Lot 5 and 6 parking lots.
- 8. Tree plan updated to match Infrastructure plan with additional surveyed trees.
- 9. Corrected floodplain limits.
- 10. West line of Lot 7 simplified.
- 11. Lot lines and areas revised to accommodate these revisions.

Building & Site • CATSO • Planning










Permits may now be issued by applicable City departments, provided that such improvements are consistent with the revised plan.


If you have any questions, please feel free to call our department at (573) 874-7239.


Sincerely,

Clint Smith, Community Development Director


Clinton.Smith@CoMo.gov







LEGEND



EXISTING PROPERTY LINE PROPOSED PROPERTY LINE 1% ANNUAL CHANCE FLOODPLAIN FLOODWAY DRAINAGE SWALE TREE & BRUSH LINE EXISTING CONTOUR AREA INLET CURB INLET FLARED END SECTION FIRE HYDRANT OUTFALL CONTROL STRUCTURE POLYVINYL CHLORIDE PIPE SIDE OPEN INLET LIGHT STANDARD PROPOSED SANITARY SEWER LINE PROPOSED WATER LINE PROPOSED GAS LINE PROPOSED STORM SEWER PROPOSED FIRE HYDRANT PROPOSED WATER VALVE

GENERAL NOTES

- a. TOTAL SITE AREA = 72.08 ACRES
- b. R/W DEDICATION = 4.849 ACRES c. EXISTING ZONING: PD — PLANNED DEVELOPMENT & A — AGRICULTURE d. PROPOSED ZONING: PD — PLANNED DEVELOPMENT
- a. DEVELOPMENT OF THE PROPERTY WILL COMPLETED IN PHASES.
- b. LOTS 1, 5, & 9 WILL REQUIRE APPROVAL OF FUTURE PD DEVELOPMENT
- c. LOT 10 WILL REQUIRE ADDITIONAL TRAFFIC IMPACT ANALYSIS. DEVELOPMENT DENSITY AND AREA WILL BE SUBJECT TO RECOMMENDATIONS OF ANALYSIS.
- d. CREEKWOOD PARKWAY AND PUBLIC UTILITIES WILL BE COMPLETED AS SHOWN TO SERVE PLAT 1. e. IMPROVEMENTS TO SERVE LOT 10 WILL BE COMPLETED AS REQUIRED TO

SERVE DEVELOPMENT OF LOT 10. LOT 10 DEVELOPMENT MAY BE

- COMPLETED IN PHASES. f. LOT 9 PRIVATE COMMON DRIVE MAY BE COMPLETED IN PHASES TO SERVE THE CONFERENCE CENTER AND HOTEL 2.
- g. LOT 7 COMMON AREA MAY BE EXPANDED TO SERVE LOT 10. 3. LOTS 3 & 7 ARE COMMON LOTS AND SHALL INCLUDE CROSS ACCESS AND UTILITY
- EASEMENTS. 4. LOT 8 SHALL BE A PRESERVATION LOT. NO DEVELOPMENT IS PERMITTED. HOWEVER, A 25 FOOT GREENSPACE TRAIL EASEMENT SHALL BE PROVIDED ALONG HINKSON CREEK AT THE REQUEST OF THE CITY OF COLUMBIA. THE LOCATION OF
- FINALIZED WITH THE FINAL PLAT.. 5. ALL BUILDINGS, UTILITIES, AND SEWERS SHOWN ARE APPROXIMATE AND SHALL BE

THE TRAIL CENTERLINE SHOWN ON THE PLAN IS PRELIMINARY AND WILL BE

- FINALIZED WITH PERMITTING PLANS AT A LATER DATE. 6. MAXIMUM BUILDING HEIGHT FOR LOTS 2 & 3 SHALL BE 85-FEET. ALL OTHER BUILDINGS SHALL COMPLY WITH THE DIMENSIONAL STANDARDS OF SECTION 29-4.1-1. ADDITIONAL BUILDING HEIGHT MAY BE REQUESTED THROUGH FUTURE PD
- 7. SITE LIGHTING SHALL BE PER THE CITY OF COLUMBIA UNIFIED DEVELOPMENT CODE
- 8. SETBACKS WILL BE PROVIDED AS SHOWN ON THE PLAN.
- 9. THE CONFERENCE CENTER AND HOTELS SHALL REQUIRE NO SEPARATION. ALL OTHER BUILDINGS SHALL BE SEPARATED BY AT LEAST 10 FEET.
- 10. DUE TO THE CLOSE PROXIMITY OF CREEKWOOD PARKWAY AND US 63, VISUAL SCREENING MAY BE NECESSARY TO MINIMIZE THE IMPACT OF HEADLIGHTS FROM NORTHBOUND US 63 VEHICLES ON SOUTHBOUND CREEKWOOD PARKWAY. SCREENING MUST BE APPROVED BY MODOT AND CITY TRAFFIC REVIEW.
- 11. NO EVIDENCE OF LAGOONS, CEMETERIES, OR BURIAL GROUNDS ARE LOCATED ON
- 13. WATER MAIN EXTENSION SHALL SERVE ALL LOTS AND CONNECT TO THE EXISIING WATER MAINS NORTH OF VANDIVER DRIVE AND WEST OF US HIGHWAY 63.
- 14. FIRE HYDRANTS SHALL BE PLACED EVERY 300—FEET, WITHIN 100—FEET OF ANY FIRE DEPARTMENT CONNECTION, OR AS REQUIRED BY THE FIRE DEPARTMENT.
- 15. SIDEWALKS ALONG PUBLIC AND PRIVATE STREETS WILL BE CONSTRUCTED WITH LOT

= 410 SPACES

TOTAL PROVIDED = 410 SPACES

16. EXISTING SANITARY SEWER BISECTS THE SITE. SANITARY SEWER SHALL BE EXTENDED TO SERVE ALL LOTS.

PARKING NOTE

<u>LOT 2</u>		
REQUIRED PARKING		
BANK	TOTAL OFFICE SF (2,400) / 300	= 8 SPAC
	TOTAL REQUIRED	= 8 SPAC
PROVIDED PARKING		
BANK		= 8 SPAC
	TOTAL PROVIDED	= 8 SPAC
<u>LOTS 4 & 6</u>	TOTAL PROVIDED	= 8 SPAC
REQUIRED PARKING		2 21112
REQUIRED PARKING HOTEL 1	151 ROOM HOTEL @ 1 STALL PER ROOM	= 151 SPA
REQUIRED PARKING HOTEL 1 HOTEL 2	151 ROOM HOTEL @ 1 STALL PER ROOM 151 ROOM HOTEL @ 1 STALL PER ROOM	= 151 SPA0 = 151 SPA0
REQUIRED PARKING HOTEL 1	151 ROOM HOTEL @ 1 STALL PER ROOM	= 151 SPA0 = 151 SPA0 = <u>231 SP</u> A0
REQUIRED PARKING HOTEL 1 HOTEL 2	151 ROOM HOTEL @ 1 STALL PER ROOM 151 ROOM HOTEL @ 1 STALL PER ROOM TOTAL CONFERENCE CENTER SF (46,096) / 200	= 151 SPA(= 151 SPA(= 231 SPA = 533 SPA

9/30/2025 PE-200700281

Engineering Surveys & Services

DELIVERING YOUR VISION ™

1113 Fay Street, Columbia, MO 65201

573 - 449 - 2646

2 El Dorado Drive, Jefferson City, MO 65

573-636-3303

1775 West Main Street, Sedalia, MO 65301

www.ess-inc.com

MO Engineering Corp. # 2004005018

SCALE: 1" = 80'

ISIO

~

O

MATTHEW A. KRIETE PROFESSIONAL ENGINEER PE-2007002811

IF ORIGINAL SIGNATURE OR DIGITAL AUTHENTICATION IS NOT PRESENT THI MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT.

AUGUST 22, 2025

Revised SEPTEMBER 11, 2025 SEPTEMBER 30, 2025

Design: ST Drawn: CGH

PD PLAN & PRELIMINARY PLAT - PLAT

ES&S PROJECT NO. 16624

PROVIDED PARKING


CLARK LANE

INTERSTATE 70

NOT TO SCALE

SIGNAGE NOTES

HOTEL/CONFERENCE CENTER



Engineering Surveys

ES&S PROJECT NO. 16624







PLANNED DEVELOPMENT PLAN FOR
LOTS 2, 4, 6, & 7
CENTERSTATE CROSSING
COLUMBIA, BOONE COUNTY, MISSOURI

Date **AUGUST 22, 2025**

Revised
SEPTEMBER 11, 2025


Design: ST Drawn: CGH

BUILDING RENDERINGS


Silect


BR1.01

ES&S PROJECT NO. 16624





TYPICAL WALL SIGN





TYPICAL DIRECTIONAL SIGNS





TYPICAL MONUMENT SIGN

LOTS 2, 4, 6, & 7

CENTERSTATE CROSSING

Date **AUGUST 22, 2025**

Revised
SEPTEMBER 11, 2025


SEPTEMBER 11, 2023

Design: ST Drawn: CGH

HYATT PLACE SIGNAGE DETAILS

SG1.01

ES&S PROJECT NO. 16624



Engineering Surveys