

### Demolition Site Plan

- 913 Range Line
- 1001 Range Line

1. All structures will be demolished completely including foundations and basements.
2. Site will be graded to drain away from the street, meeting existing elevations at the perimeters.
3. All bare ground will be seeded and strawed following cleanup.

