BUSINESS | PD PLAN FOR LLOOP 70 KINNEY POINT LOCATED IN SECTION 12, TOWNSHIP 48 NORTH, RANGE 13 WEST COLUMBIA, BOONE COUNTY, MISSOURI ------J WORLEY STREET EXISTING BUILDING LOCATION MAP NOT TO SCALE (11)(13) $(\overline{14})$ $(\overline{15})$ LEGEND: $(\overline{16})$ ______ EXISTING 2FT CONTOUR - - -820- - EXISTING 10FT CONTOUR STEPHANIE YOHN WARRANTY DEED CITY OF COLUMBIA FENCO RENTALS LLC DALE & MICHELLE AMANN ALLEN, DOROTHY L WARRANTY DEED - — -S- — - Existing sanitary sewer TRUSTEES DEED BOOK 4990, PAGE 147 R-2 ZONING BOOK 2975, PAGE 49 WARRANTY DEED BOOK 4812, PAGE 84 BOOK 5305, PAGE 112 R-2 ZONING BOOK 1226, PAGE 123 RENTALS LLC PROPOSED SANITARY SEWER R-2 ZONING WARRANTY DEED / BOOK 5691, MANHOLE/CLEANOUT PAGE 181 R-2 ZONING PROPOSED WATERLINE 15' PUBLIC ALLEY 15' PUBLIC ALLEY S 89°19'35" E 576.34' PROPOSED LIGHT POLE PROPOSED FIRE HYDRANT $(\overline{10})$ 8' BUILDING SETBACK LINE <u>o' buildin</u>ig <u>setb</u>ack_ ===== Existing storm sewer BÚILDING 9 PROPOSED STORM SEWER 2-STORY SBUILDING 7 💉 2-UNITS TYPE C 1-STORY 2.95 ACRES 2-UNITS — — — — EASEMENT DUPLEX LOT NUMBER GARTH BUILDING 10 EXISTING LOT NUMBER 2-STORY PROPOSED PAVEMENT PROPOSED DETENTION/BIORETENTION BUILDING 8 BUILDING 2 1-STORY 3-STORY 2-UNITS EXISTING TREE BÚÍLÓÍNG 11 DUPLEX DUPLEX 2-STORY --- W --- EXISTING WATER LINE 3-STORY —— · · —— DETENTION FACILITY

4-UNITS

 $(\overline{2})$

" BUILDING 5, 1/4.

BUILDING 6

3-STORY

4-UNITS

 $\left(\begin{array}{c} \overline{1} \end{array}\right)$

STORM SEWER

DETENTION AREA

 $\begin{bmatrix} \overline{6} \end{bmatrix}$

· 3-STORY ...

4-UNITS

SCALE: 1"=30'

THE HOUSING AUTHORITY OF THE CITY OF COLUMBIA 201 SWITZLER ST COLUMBIA, MO 65203 573-443-2556

LEGAL DESCRIPTION:

A TRACT OF LAND LOCATED IN THE NORTHWEST QUARTER OF SECTION 12, TOWNSHIP 48 NORTH, RANGE 13 WEST, COLUMBIA, BOONE COUNTY, MISSOURI AND BEING PART OF THE LAND DESCRIBED BY THE WARRANTY DEED RECORDED IN BOOK 4076, PAGE 124 AND BEING ALL OF LOT 1-A & 1-B OF GRACE COVENANT CHURCH SUBDIVISION, PLAT 1-A, RECORDED IN PLAT BOOK 46, PAGE 12 AND CONTAINING 2.95 ACRES.

— — — — ESTIMATED BUILDING ENVELOPE

1) A REQUEST IS BEING MADE FOR A DESIGN EXCEPTION FROM THE UDC SECTION 29-4.3(B) REGARDING REQUIRED PARKING FOR RESIDENTIAL USE DWELLINGS. THIS PROJECT REQUESTS THAT PARKING FOR THIS DEVELOPMENT TO BE REDUCED BY 18 PARKING SPACES DUE TO THE PROPOSED USES.

5' OF ADDITIONAL RIGHT OF WAY TO BE GRANTED

 $(\overline{4})$

LOCATION OF THE 1,00-YEAR FEMA FLOODPLAIN

 $(\overline{3})$

2) A REQUEST IS BEING MADE FOR A DESIGN EXCEPTION FROM THE UDC SECTION 29-2.2(a)(3)-R-MF MULTIPLE-FAMILY DWELLING DISTRICT, REGARDING SETBACKS. A REQUEST TO REDUCE THE REAR YARD SETBACK FROM 25 FEET TO 10 FEET IS BEING REQUESTED ALONG THE NORTH EDGE OF THE PROPERTY ADJACENT TO THE ALLEY. ADDITIONALLY, A REQUEST TO REDUCE THE FRONT YARD SETBACK FROM 25 FEET TO 20 FEET IS BEING REQUESTED ALONG THE SOUTH EDGE OF THE PROPERTY ADJACENT TO THE SEXTON ROAD.

DESIGN ADJUSTMENT

DESIGN EXCEPTIONS

R= 30.00'

L= 36.74'

34.49'

CH=S 33°52'55" E

1) A REQUEST IS BEING MADE FOR A DESIGN ADJUSTMENT TO SECTION SEC. 29-5.1(C)(4)(II) FROM THE UDC FOR RELIEF ON ADDITIONAL RIGHT-OF-WAY FOR GRAND AVENUE AND THE ALLEY STREET.

NOTES:

- 1. SITE CONTAINS 2.95 ACRES.
- 2. IT IS THE INTENT OF THIS DEVELOPMENT TO BE COMPLETED IN ONE PHASE.
- 3. EXISTING ZONING IS PD.
- 4. PART OF THIS TRACT IS LOCATED IN THE 1% ANNUAL CHANCE FLOOD PLAIN AS SHOWN BY FEMA FIRM, PANEL NUMBER 29019C0280E, DATED APRIL 19, 2017.
- 5. ALL LIGHTING SHALL BE IN ACCORDANCE WITH THE CITY OF COLUMBIA LIGHTING ORDINANCE. ALL LIGHTING SHALL BE SHIELDED AND DIRECTED INWARD AND DOWNWARD AWAY FROM RESIDENCES, NEIGHBORING PROPERTIES, PUBLIC STREETS, AND OTHER PUBLIC AREAS.
- 6. NO PART OF THIS TRACT IS LOCATED WITHIN CITY STREAM BUFFER AS DETERMINED BY THE USGS MAP FOR COLUMBIA QUADRANGLE, BOONE COUNTY, MISSOURI AND ARTICLE X OF CHAPTER 12A OF THE CITY OF COLUMBIA CODE OF ORDINANCES.
- 7. THE MAXIMUM HEIGHT OF ANY BUILDING WILL NOT EXCEED 35', AS MEASURED BY THE CITY OF COLUMBIA STANDARDS.
- 8. THIS LOT IS SUBJECT TO THE CITY OF COLUMBIA STORMWATER ORDINANCE CHAPTER 12A, WATER QUALITY AND DETENTION REQUIREMENTS. THIS PLAN IS CONCEPTUAL AND A FULL STORMWATER MANAGEMENT PLAN WILL BE PROVIDED WITH CONSTRUCTION DOCUMENTS. FUTURE DETENTION SHALL BE DESIGNED TO LIMIT THE POST-DEVELOPMENT RELEASE RATES TO THE PRE-DEVELOPMENT FLOW RATES FOR THE 100-YEAR EVENT FOR LOTS 1-A & 1-B GRACE COVENANT CHURCH SUBDIVISION PLAT 1-A AND LOT 2, GRACE COVENANT CHURCH SUBDIVISION. WATER QUALITY FOR THESE LOTS SHALL TREAT NEW IMPERVIOUS AREAS TO A LEVEL OF SERVICE OF 3.
- 9. STORM WATER QUALITY STANDARDS SHALL BE MET BY USING BMP'S COMPLYING WITH THE CITY OF COLUMBIA STORMWATER REGULATIONS OFF-SITE. SOME BMP'S MAY BE ALLOWED OFF-SITE UPON APPROVAL BY THE CITY'S STORM WATER ENGINEER.
- 10. ALL DRIVE, ROADWAY, AND ACCESS AISLE ARE SUBJECT TO FIRE DEPARTMENT APPROVAL AT THE TIME OF FINAL DESIGN.
- 11. THE MAXIMUM RELEASE RATE FROM THIS DEVELOPMENT SHALL BE CONTROLLED BY LIMITING THE POST-DEVELOPMENT STORM WATER RELEASE RATES TO THE PREDEVELOPMENT RATES FOR THE 1, 2, 10 AND 100 YEAR STORMS.

PARKING CALCULATIONS: SPACES REQUIRED DWELLING MULTI FAMILY: 1.5 SPACES/DWELLING UNIT FOR 1 BEDROOM UNITS * 10 UNITS 15 SPACES SPACES/DWELLING UNIT FOR 2 BEDROOM UNITS * 6 UNITS 12 SPACES 2.5 SPACES/DWELLING UNIT FOR 3 BEDROOM UNITS * 8 UNITS 20 SPACES 2.5 SPACES/DWELLING UNIT FOR 4 BEDROOM UNITS * 10 UNITS 25 SPACES GUEST PARKING: 1 SPACES/5 DWELLING UNITS 34/5 7 SPACES TOTAL SPACES REQUIRED: 79 SPACES SPACES PROVIDED 61 SPACES TOTAL SPACES PROPOSED: AREA & DENSITY CALCULATIONS: TOTAL LOT AREA = 2.95 ACRES PROPOSED NUMBER OF UNITS: PROPOSED DENSITY: 11.50 UNITS / ACRE APPROXIMATE IMPERVIOUS AREA = 67,663 S.F. (52.65%)

NOTE: IMPERVIOUS AREA CALCULATIONS ABOVE REFLECT THE SITE PLAN ON THIS SHEET. IMPERVIOUS AREA MAY CHANGE DURING FINAL PLANS. TOTAL IMPERVIOUS AREA SHALL NOT EXCEED 60%.

APPROVED BY ORDINANCE OF THE CITY COUNCIL OF COLUMBIA, MISSOURI THIS DAY OF ______, 2023.

BARBARA BUFFALOE, MAYOR

ATTEST:

SHEELA AMIN, CITY CLERK

APPROVED BY THE CITY OF COLUMBIA PLANNING AND ZONING COMMISSION

SHARON GEUEA JONES, CHAIRPERSON

THIS SHEET HAS BEEN SIGNED, SEALED AND

≅ ₹20' FRONT SETBACK LINE

S89°16'25"E

72.98'

COLUMBIA SCHOOL DISTRICT

WARRANTY DEED BOOK 1969, PAGE 857

PD ZONING

COLUMBIA SCHOOL DISTRICT


WARRANTY DEED

BOOK 1969, PAGE 857

PD ZONING

PROPOSED PRIVATE WATER LINE

(TO REMAIN)



PREPARED BY: CRECKETT ENGINEERING CONSULTANTS


1000 W. Nifong Blvd., Bldg 1 Columbia, Missouri 65203 (573) 447-0292 www.crockettengineering.com

REV 1 05/23/2023

ORIGINAL 05/01/2023

PD PLAN FOR KINNEY POINT





	LANDSCAPE COMPLIANCE:						
	29-4.4(c) - GENERAL PROVISIONS:						
	EXISTING CLIMAX FOREST: CLIMAX FOREST TO REMAIN:	0 AC. 0 AC.					
	REQUIRED 15% OF TOTAL SITE TO BE LANDSCAPED: PROPOSED AREA OF TOTAL SITE TO BE LANDSCAPED:	0.44 AC. 1.40 AC.					
	29-4.4(d) - STREET FRONTAGE LANDSCAPING:						
	WIDE 0 L.F.						
	1 TREE (2" CALIPER, 10' TALL AT TIME OF PLANTING) PER 200 S.F. OF BUFFER AREA	0 TREES					
A	(2)(i) 1 TREE PER 60' STREET FRONTAGE: (832' STREET FRONTAGE) (ii) 30% LARGE TREES MIN. 5 TREES OTHER TREES 3 TREES	14 TREES					
	EXISTING STREET TREES NET STREET TREES TO BE PLANTED 29-4.4(e) - PROPERTY EDGE BUFFERING:	13 TREES					
	(1) SEE PLAN FOR TABLE 4.4–4 DETERMINED LEVEL OF SCREENING AND BUFFERING. LEVEL 1 SCREENING TO BE PROVIDED ALONG NORTH AND EAST PROPERTY LINES.						
	29-4.4(f) - PARKING AREA LANDSCAPING:						
	(1) IF PARKING AREA CONTAINS MORE THAN 100 SPACES, PARKING SPACE AREA TO INCLUDE LANDSCAPING AREA EQUAL TO 10% OF PAVED AREA, WI TREE PER 40' L.F. OF LANDSCAPED AREA.	N/A TH 1					
B	(4) 1 TREE PER 4,000 S.F. OF PARKING PAVED AREA — 23,518 S.F. 6 TREES EXISTING PARKING LOT TREES O TREES NET PARKING LOT TREES TO BE PLANTED	6 TREES					
	29-4.4(g) - PRESERVATION OF EXISTING LANDSCAPING:						
©	TOTAL SIGNIFICANT TREES: 25% OF SIGNIFICANT TREES TO BE PRESERVED: 4 TREES TOTAL SIGNIFICANT TREES TO BE REMOVED: 8 TREES						


	QUANTITY	COMMON NAME	BOTANICAL NAME	PLANT TYPE	SIZE
*	5	RIVER BIRCH	BETULA NIGRA "HERITAGE"	LARGE TO MEDIUM TREE	2.5" CALIPER
	6	BLACK TUPELO	NYSSA SYLVATICA	LARGE TO MEDIUM TREE	2.5" CALIPER
P	9	IMPERIAL HONEYLOCUST	GLEDITSIA TRIACANTHOS "IMPCOLE"	MEDIUM/LARGE TREE	2" CAL. & 10' TALL
	24	DWARF KOREAN LILAC	SYRINGA MEYERI 'PALIBIN'	SMALL DECIDUOUS SHRUB	5 GALLON
Manual Ma	30	DWARF DAYLILY	HEMEROCALLIS 'STELLA DE ORO'	PERENNIALS FOR SUN	N/A
	18	PRAIRIE DROPSEED	SPOROBOLUS HETEROLEPIS	GRASS	N/A
	N/A	EXISTING GRASS			

TYPICAL PROPERTY EDGE BUFFERING BED PLANTING DETAIL

PLANTING NOTES:				
	QUANTITY	PLANT SPECIES		
	14	LARGE/MEDIUM TREE		
	5	SMALL/ORNAMENTAL TREE		

LANDSCAPING NOTES:

- 1. 1. ALL DISTURBED AREAS SHALL BE SEEDED & MULCHED AFTER CONSTRUCTION.
- 2. 2. LANDSCAPING MAY BE ENHANCED BY THE DEVELOPER AS TIME AND BUDGET ALLOWS.
- 3. 3. ALL PLANT MATERIALS AND FINAL LANDSCAPE PLAN SHALL BE IN ACCORDANCE WITH THE LANDSCAPING GUIDELINES AND STANDARDS OF THE CITY OF COLUMBIA.
- 4. LANDSCAPING SHALL COMPLY WITH SECTION 29-4.4 OF THE CITY OF COLUMBIA CODE
- OF ORDINANCES.
- 5. 6. THIS LANDSCAPING PLAN IS CONCEPTUAL IN NATURE. PRECISE LOCATION AND SPECIES INFORMATION MUST BE APPROVED AT THE SITE PLAN STAGE AND MAY NOT EXACTLY MATCH WHAT IS SHOWN GRAPHICALLY.



PREPARED BY:

ENGINEERING CONSULTANTS

1000 W. Nifong Blvd., Bldg 1 Columbia, Missouri 65203 (573) 447-0292 www.crockettengineering.com

TIMOTHY D. CROCKETT, P.E. 2004000776

BUSINESS |

EXISTING 2FT CONTOUR

EXISTING LOT NUMBER

PROPOSED PAVEMENT

____ OE ___ EXISTING OVERHEAD ELECTRIC

__ _ _ _ ESTIMATED BUILDING ENVELOPE

___ W ___ EXISTING WATER LINE

____ . . ____ DETENTION FACILITY

SCALE: 1"=30'

OWNER

THE HOUSING AUTHORITY OF THE CITY OF COLUMBIA 201 SWITZLER ST

COLUMBIA, MO 65203

573-443-2556

PROPOSED DETENTION/BIORETENTION

LOCATION MAP NOT TO SCALE

LEGEND:

JL LOOP 70